

STATE OF ILLINOIS
LAKE COUNTY DIVISION OF TRANSPORTATION
600 W. WINCHESTER ROAD
LIBERTYVILLE, ILLINOIS

Notice is hereby given that sealed bids will be received at the office of the County Engineer at the Lake County Division of Transportation office at 600 W. Winchester Road, Libertyville, Illinois until 10:00 a.m. on **May 17, 2016** for the following:

Section 15-00999-10-DR **Detention Basin Retrofits**

Consists of earth excavation, riprap, storm sewer and drainage structure removal and installation, landscaping and other related items.

Major contract items and estimated quantities are summarized as follows:

QTY	UNIT	MAJOR BID ITEM
63,163.00	SQ FT	SEEDING, SPECIAL I
45.00	UNIT	PERENNIAL PLANTINGS, WETLAND TYPE, SPECIAL II
30,974.00	SQ FT	SEEDING, SPECIAL II
899.00	CU YD	EARTH EXCAVATION
26.00	UNIT	PERENNIAL PLANTINGS, WETLAND TYPE, SPECIAL III

Section 16-00000-05-GM **2016 Clean and Televisе Storm Sewer**

The work consists of cleaning existing storm sewer, inspecting existing drainage structures (inlets, manholes and catch basins); televising the existing storm sewer and furnishing a condition report including video and photographic records. The project includes traffic control and protection and other related work.

Major contract items and estimated quantities are summarized as follows:

QTY	UNIT	MAJOR BID ITEM
2,658.00	FEET	CLEAN AND TELEVISE STORM SEWER 12", 15", 21" & 24"
200.00	FEET	ROOT REMOVAL
270.00	FEET	HEAVY CLEANING
31.00	EACH	DRAINAGE STRUCTURE INSPECTION
1.00	LUMP SUM	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)

Section 16-00000-12-GM

2016 Reflective Pavement Markers

This works consists of removing white reflector Raised Reflective Pavement Markers and replacing them with white reflector Recessed Reflective Pavement Markers. The project limits, county highways & reflective pavement markers included, are as described herein and/or as directed by the Engineer. Traffic Control and Protection is required for this project.

Major contract items and estimated quantities are summarized as follows:

QTY	UNIT	MAJOR BID ITEM
5,699.00	EACH	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL
5,657.00	EACH	RECESSED REFLECTIVE PAVEMENT MARKER
1	LUMP SUM	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)

Section 16-00000-15-GM

2016 Pavement Marking Replacement

Remove and replacing thermoplastic pavement markings on existing HMA highways and removing and replacing polyurea pavement markings on existing concrete highways. The work will be performed at various locations on Lake County highways; City of Highland Park Streets and parking areas; and Village of Wheeling Streets. Separate contracts shall be awarded and administered by each community or unit of government. The following quantities are a composite of the community and county totals. The individual project totals are listed in the contract specifications. Traffic control and protection is required for this project.

Major contract items and estimated quantities are summarized as follows:

QTY	UNIT	MAJOR BID ITEM
12,282.40	SQ FT	THERMOPLASTIC PAVEMENT MARKING – LETTERS & SYMBOLS
433,636.00	FT	THERMOPLASTIC PAVEMENT MARKING – LINE 4”, 6”, 8”, 12” & 24”
1,781.00	SQ FT	POLYUREA PAVMENT MARKING TYPE I – LETTERS & SYMBOLS
19,683.00	FEET	POLYUREA PAVEMENT MARKING TYPE I - LINE 4”, 6”, 8”, 12” & 24”
218,589.00	SQ FT	PAVEMENT MARKING REMOVAL

Section 16-00249-04-RS

Buffalo Grove Patching

The pavement patching consists of partial depth hot-mix asphalt patching of concrete pavement, including 2” milling of the existing concrete pavement and resurfacing with 2” of hot-mix asphalt surface course. The work also includes full depth patching (10”) of the concrete pavement with hot-mx asphalt; milling and resurfacing existing HMA turn lanes; removing and replacing existing HMA

turn lanes and HMA shoulders and other related work. Traffic Control and Protection is required for this project.

Major contract items and estimated quantities are summarized as follows:

QTY	UNIT	MAJOR BID ITEM
473.00	TONS	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70
540.00	TONS	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70
192.00	SQ YDS	CLASS D PATCHES, TYPE II, 10 INCH
1,728.00	SQ YDS	PORTLAND CEMENT CONCRETE SURFACE REMOVAL 2"
2,909.00	SQ YDS	PAVED SHOULDER REMOVAL

Section 16-08101-01-GM **Grant Road District - 2016**

The project consists of a 3 3/4 " Hot-Mix Asphalt Surface Removal; Base repair with undercut contingencies; and Resurfacing with Hot-Mix Asphalt Binder and Surface courses. This project will be constructed under Traffic with Temporary Ramps and Aggregate for Temporary Access included. Traffic Control and Protection, (Special) for the work zone is required.

Major contract items and estimated quantities are summarized as follows:

QTY	UNIT	MAJOR BID ITEM
568.00	TON	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50
378.00	TON	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50
4,100.00	SQ YD	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"
4,100.00	SQ YD	PREPARATION OF BASE
1.00	LUMP SUM	TRAFFIC CONTROL AND PROTECTION (SPECIAL)

Section 16-16000-01-GM **Waukegan Road District**

The project consists of overlaying the existing pavement with 1 1/2" of Hot -Mix Asphalt Surface Course. Butt joints will be cut to tie back into the existing pavement. Traffic Control and Protection for the work zone is required.

Major contract items and estimated quantities are summarized as follows:

QTY	UNIT	MAJOR BID ITEM
851.00	TON	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50
811.00	SQ YD	HOT-MIX ASPHALT SURFACE REMOVAL – BUTT JOINT
4,554.00	POUND	BITUMINOUS MATERIALS (TACK COAT)
1.00	LUMP SUM	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)

ELECTRONIC PLANS AND SPECIFICATIONS FOR THE ABOVE PROJECT(S)
WILL BE AVAILABLE : April 28, 2016
ON THE LAKE COUNTY DIVISION OF TRANSPORTATION WEBSITE at
<http://www.lakecountyil.gov/648/Bids---Roadwork>

All bid packages are available at no charge on the LCDOT website at <http://www.lakecountyil.gov/648/Bids---Roadwork>. The entire letting set is also available on CD-ROM for \$20.00, payable by cash, company check or money order made out to Treasurer of Lake County. Bid packages are available in electronic format *only*.

Bidders must obtain an **Authorization to Bid** prior to the letting. To receive authorization, bidders shall fill out Part A and Part C of the **Request for Authorization to Bid** (available on the LCDOT website at <http://www.lakecountyil.gov/648/Bids---Roadwork> and submit this form along with a copy of their current Prequalification Rating Notice issued by IDOT to the Lake County Division of Transportation via email or fax. Proposals from bidders that have not received authorization to bid will not be opened and read. Subcontractors and suppliers that would like to be placed on the Not For Bid plan pick up list must also submit a Request for Authorization to Bid, filling out Part B and Part C.

A 5% security deposit or bid bond must accompany the bid. The successful bidder must furnish a satisfactory performance bond and a payment bond each in the full amount of the bid.

The Prevailing Wage Act (820 ILCS 130), as amended, shall apply to all contracts entered into pursuant to this advertisement.

Lake County, in accordance with laws of the State of Illinois, hereby notifies all bidders that it will affirmatively ensure that all contracts entered into pursuant to this advertisement will be awarded to the lowest responsible bidder without discrimination on grounds of race, color or national origin.

By: RuthAnne K. Hall
Purchasing Agent

(NewSun) PLEASE PUBLISH 4/28 and 5/5