NOTE:
REFER TO SHEET 23 FOR ENLARGED PLAN & DETAILS OF NEW WORK AT PLANTER AREAS.

BREAKMETAL COVER TO MATCH GLAZING FRAMES - PROVIDE IDENTICAL CLOSURES AS DIMENSIONED BELOW
2-LAYERS 5/8" GYP. BD. AROUND EXIST. COL.
NEW INSUL. GLASS IN ANOD. ALUM. THERMAL-BREAK FRAME
SEAL CONT. ALL AROUND - TYP.
BREAKMTL. FACE CLOSURE TO MATCH FRAMING

DETAIL 1
1½" = 1'-0"

STAIR 203
STORAGE 204
CORRIDOR 205
TEMP. COURTROOM 224
TEMP. COURTROOM 223
JAN. 210
CORRIDOR 206
MEN 211
WOMEN 209
VESTIBULE 215
LOUNGE 212
DISPATCH 216
GEAR STOR. 214
CPL. & LT. OFF. 213
RAMP
EXIST. COURTROOM
PUBLIC LOBBY 217
PUBLIC LOBBY 218
CORRIDOR 208
CORRIDOR 207
JURY ASSEMBLY 222
JURY CLERK 221
JURY COORDINATOR 220
GUN LOCK-UP 219
STAIR 201
ENTRY LOBBY 202

EXIST'G PLANTER
NEW PLANTER SILL
EXIST'G PLANTER SILL
LINE OF STONESILL ABOVE
REMOVE & REPLACE GLASS W/ OPAQUE SPANDREL GLASS
STORAGE LOCKERS - SEE SPECS.
2-HOUR MECH. CHASE
EXIST'G STAIR
EXIST'G ELEV.
REMOVE GLASS & FRAME & INSTALL 3 5/8" MTL. STUDS W/ 2-LAYERS 5/8" TYPE 'X' GYP. BD. WALL TIGHT TO UNDERSIDE OF CONSTRUCTION ABOVE - RE. INSTALL BASEBD. AFTER ERECTION
EXIST. BASE BD. HEATER
SEE SHT. 38 FOR INTERIOR ELEVATIONS
SEE SHEET 39 FOR INTERIOR ELEVATIONS
OUTSIDE PLAZA
FURR OUT EXIST. CONC. COLS. W/ 1½" MTL. FURR'G & 5/8" GYP. BD.
FURR OUT AROUND EXIST. COLS. W/ 2-LAYERS 5/8" TYPE 'X' GYP. BD.
PARTITION JAMB @ WINDOWS
ELEC. PARTITION - TYP. FOR 2-THUS
POCKET DOORS & FRAME BY PARTITION MFR. - TYP.
COUNTER (N.I.C.)
REPLACEMENT WINDOWS: ANOD. ALUM. THERMAL BREAK FRAMING W/ INSULATING GLASS
FINISH MATERIALS OVER 2-HR. 2-LAYERS 5/8" TYPE 'X' GYP. BD. COL. ENCLOSURE - TYP.
2-LAYERS 5/8" TYPE 'X' GYP. BD. AROUND EXISTING COLUMN
2-HR. CHASE FOR MECH. USE
VIDEO MONITOR DISPLAY NICHE W/ PAINTED GYP. BD. WALLS, CEILING & BIRCH FACED PLYWD. SHELF - SEE 4/36
CONSTRUCTION WORKING POINT
LINE OF EXIST. FND. WALL BELOW
TYPICAL MULLION SPACING
LINE/ EXIST. STONE SILL
EXIST. STONE CLAD COLS. - TYPICAL
BULLET PROOF ARMOR ON FURRING @ WALLS & CEILING - COVER W/ GYPSUM BOARD
WALL MTD. GUN LOCKERS - SEE SPECS.
OPEN ABOVE
LINE/ FDN. BELOW
EDGE/ EXIST. STONE SILL
LINE/SKYWALK ABOVE (N.I.C.)
EXIST. STONE STAIRS TO BE REMOVED - SEE DEMO PLAN
EXIST. PLANTER TO REMAIN

NOTE:
REFER TO SHEET 16 FOR ENLARGED PLAN & DETAILS OF NEW ENTRANCE ADDITION

TYPICAL WALL TYPES
- FULL HEIGHT SOUND ATTENTUATION INSUL. IN METAL STUD PARTITION W/ 1 OR 2-LAYERS GYP. BD. FOR 1 OR 2 HR. RATING, TIGHT TO DECK
- CONCRETE BLOCK PARTITION W/ FURRING AND GYPSUM BOARD FULL HEIGHT
- FACE BRICK W/ CONC. BLOCK; FURRING FOR GYP. BD. OR MATERIALS AS NOTED
- EXISTING WALL OR PARTITION

ABOVE ARE TYPICAL FOR ALL FLOORS

SECOND FLOOR PLAN
1/8" = 1'-0"

REVISIONS	BY

SUTTER & SCHROEDER ARCHITECTS, LIMITED
131 EAST PARK AVENUE • SUITE A
LIBERTYVILLE, IL 60048 708:362:3600
architects • planners • engineers

EXPANSION AND RENOVATIONS TO THE LAKE COUNTY COURTS FACILITIES
18 NORTH COUNTY WAUKEGAN, IL

DRAWN	
CHECKED	
DATE	7-29-93
SCALE	
JOB NO.	5141
SHEET	8 OF 58 SHEETS

TELEDYNE POST 18AL-20 – 24 x 36